

Work under the Contract 0700684 includes, but is not limited to:

**Berry Sewerage Treatment Plant Site**

- Weed/grass eradication from all proposed planted areas;
- Temporary fencing to protect the works outside the STP fence from dairy farm activities;
- Grading of area between earth mound on western side of the site and STP manproof fence to improve the existing drainage swale and to eliminate water pooling in the area;
- Mulching;
- Supply and install native grass tubestocks including fertiliser and water retaining polymer;
- Supply and install tree tubestocks including stake, tie, mesh, fertiliser and water retaining polymer;
- Minimum of six (6) fortnightly establishment/maintenance visits to water all plants, replace failed and damaged plants, rubbish removal, reinstatement of mulch, weeding and upkeep of plant guards.

**Berry Sewage Pumping Station 8 Site**

- Weed/grass eradication from all planted areas;
  - Removal of existing timber paling fence;
  - Installation of new 1.8m colorbond fence to the southern boundary of the site;
  - Installation of timber post and wire fence to the northern and eastern boundaries of the pump station site;
  - Mulching;
  - Supply and install native grass tubestocks including fertiliser and water retaining polymer;
  - Supply and install tree tubestocks including stake, tie, mesh, fertiliser and water retaining polymer;
  - Removal of disused gravel driveway and replace with turf;
- Minimum of six (6) fortnightly establishment/maintenance visits to water all plants, replace failed and damaged plants, rubbish removal, reinstatement of mulch, weeding and upkeep of plant guards.