

**AIR COOLING & AIR CONDITIONING TO NOMINATED SCHOOLS  
for the  
DEPT OF EDUCATION & TRAINING  
CONTRACT 0800221**

**DESCRIPTION OF THE WORKS**

**Cowra High School**

Supply and install five evaporative cooling systems to five classrooms, one in Block A, three in Block B and one in Block D.

Four evaporative cooling systems are to be installed on the roof and the fifth is at ground level.

**Parkes East Public School**

Supply and install six evaporative cooling systems to six classrooms. Four are to be installed in Block C and two in Block D.

All systems are to be installed at ground level with ductwork penetrating the windows.

The three existing evaporative cooling units currently servicing Blocks C & D are to be removed and handed back to the School Principal.

Make good to the building following the removal.

**Quandialla Central School**

Install 6 reverse cycle air conditioning units into an 8 module demountable administration building.

The six air conditioning units are supplied by the Principal.

Supply and install steel condenser support frames to demountable building.

Supply and install supply air fans to nominated rooms

Provide all electrical circuits to existing distribution board.

Remove the existing evaporative cooler, ductwork, grilles and controls and make good to the building following the removal.

Remove the existing air conditioning unit and controls and make good to the building following the removal.

Hand the evaporative cooler and air conditioning unit to the School Principal.

**END OF DESCRIPTION OF WORKS**