

**KANDOS HIGH SCHOOL  
ALTERATIONS TO BLOCK F & PROVISION OF STORAGE SHED  
for the  
DEPT OF EDUCATION & TRAINING  
CONTRACT 0800078**

**DESCRIPTION OF THE WORKS**

- Removal of existing wall between Industrial Arts Classroom, FR0011 and verandah, demolition of Store Room, FR0012, construction of a new wall to incorporate verandah area and Store Room area into the Industrial Arts classroom.
- Provision of new lighting and power.
- Relocation of existing light switches, master control, start/stop station for dust extraction system.
- Provision of new power to new Industrial Arts machinery equipment
- Relocation of Industrial Arts machinery equipment and installation of new machinery.
- Alterations and additions to existing dust extraction ductwork to new and relocated machinery equipment.
- Construction of new 6m x 6m x 2.4m colour bond steel storage shed with concrete floor
- Provision of electrical load centre, lighting, power and security to Storage Shed.
- Remove existing electrical distribution switchboard, DB6 and provide new distribution board.
- Connect new Industrial Arts machinery equipment into Master Control circuitry.
- Make good and restore to original condition all disturbed surfaces.
- Flashings to all ducts, conduits etc, which penetrate walls or flooring.
- All lifting and hoisting equipment.
- Painting and labelling of the completed installation.
- Commissioning and testing of dust extraction systems.
- Provision of operating and maintenance manuals, including “as installed” drawings, completed test reports and equipment data.

**END OF DESCRIPTION OF WORKS**